



Sedibeng District Municipality

SPECIFICATION: 8/2/22-2011

SPECIFICATIONS: BANANA ROOM EVAPORATOR AND 7; 5HP COMPRESSOR
SPECIFICATION COMPRESSORS

DESCRIPTION

SUMMARY OF SCHEDULES

DESCRIPTION	
SECTION A:	
Add 14% VAT	
Total – Carried forward to Tender	

SCORE CARD

Minimum Technical Requirements

No	Category
1.	Three completion Certificates of similar works
2.	Track Record
3.	Construction Programme
4.	Safety Plan

Failure to submission of all the above will lead to immediate disqualification

1. Construction programme will asses aspects such as

- Construction duration
- Construction Items Duration
- Construction Items Grouping and linkage

NB: Construction Programme should be compiled using computerized project programme, Occupational Health and Safety Requirements to be attached,

BANANA ROOM EVAPORATOR AND 7; 5HP COMPRESSOR SPECIFICATION
COMPRESSORS

SPECIFICATIONS

- Re-build 2x7.5HP compressors.
- Mod PR 750 L –Copland compressor

EVAPORATOR

- Strip out and install new evaporator and commissioned.
- Complete leak test to be done on completion.

SPECIFICATIONS

- 20kw cooling
- 3x360mm Diameter SC Axial fans.Del 1.89m³ KPA & 1400RPM with a 1.1 kw motor
- 6x10kw re-heat elements for heating
- 90 Galvanized steel/powder coated
- Stainless steel drain pan with hot dipped screws
- Allow for re-seal of evap for air flow